

City of Keene Minor Project Review Committee

Pre-submission Meeting

AGENDA

Thursday, September 5, 2024 9:00 AM City Hall, 2nd Floor Conference Room

- I. Call to Order Roll Call
- II. Scheduled Pre-submission Inquiries
 - a. <u>Conceptual Subdivision Application</u> The ~7.1-ac parcel at 0 Old Walpole Rd (TMP #503-005-000) is owned by Monadnock Habitat for Humanity Inc. and is located in the Rural District.
 - **b.** Conceptual Site Plan Application The ~3.53-ac parcel at 0 Ashuelot St (TMP #567-001-000) is owned by JRR Properties LLC and is located in the High Density District.

III. Walk-in Pre-submission Inquiries

IV. Upcoming Meeting Dates

- Pre-submission Meeting Thursday, October 3, 2024 at 9:00 am
- 1st Monthly MPRC Meeting Thursday, October 3, 2024 at 10:00 am
- 2nd Monthly MPRC Meeting Thursday, October 17, 2024 at 10:00 am (If needed)


TWO LOT RESIDENTIAL SUBIDIVISION

OLD WALPOLE ROAD, KEENE, NEW HAMPSHIRE

PREPARED FOR:

MONADNOCK HABITAT FOR HUMANITY

P.O. BOX 21 KEENE, NH 03431 (781) 760-3636



INDEX OF PLANS

-1 NOTES AND DETAILS

S-1 EXISTING CONDITIONS

C-1 SITE PL

C-2 LOT 1 SEPTIC

C-3 LOT 2 SEPTIC

PREPARED BY

Wetland Scientist:

Danforth Environmental Consulting, LLC 654 New Boston Road

PHONE (603) 547-7100

Francestown, NH 03043

Land Planner:

Monadnock Land Planning, LLC 139 Old Walpole Road Keene, NH 03431

PHONE (603) 209-3050

Civil Engineer:

SVE Associates

439 West River Road Brattleboro, Vermont 05302

PHONE (802) 257-0561

Land Surveyor:

David A. Mann Survey

40 Gulf Road Chesterfield, New Hampshire 03443

PHONE (603) 903-7259

August 5, 2024

K2777

05-AUG-24

MONADNOCK
HABITAT FOR HUMANITY
2 of 11

Drawing name: P:\Project\NH PROJECTS\K2777 Habitatfor Hu

GENERAL CONSTRUCTION NOTES:

- THE CONTRACTOR SHALL CALL DIG-SAFE, AT 1-888-344-7233 AT LEAST 72 HOURS BEFORE THE START OF EXCAVATION
- 2. THE CONTRACTOR IS EXPECTED TO BE AWARE OF AND COMPLY WITH ALL PERMITS AND PERMIT CONDITIONS.
- 3. ALL TRENCHING, EXCAVATION, SHEETING, SHORING, ETC. SHALL COMPLY WITH THE MOST CURRENT OSHA REGULATIONS.
- 4. THE CONTRACTOR SHALL NOTIFY SVE ASSOCIATES IF FIELD CONDITIONS VARY FROM THAT SHOWN ON THE PLAN(S). THE CONTRACTOR'S WORK
- SHALL NOT VARY FROM THE PLAN(S) UNLESS SO AUTHORIZED BY SVE ASSOCIATES. 5. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH SITE PLANS AND SPECIFICATIONS PROVIDED OR IN ACCORDANCE WITH NH DEP'T OF
- TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION. 6. IN CASE OF CONFLICTS, THE MOST STRINGENT INTERPRETATION OF THE PLANS, SPECIFICATIONS, LOCAL OR STATE REGULATIONS, OR PERMIT
- CONDITIONS SHALL APPLY. THE ENGINEER SHALL BE THE DETERMINANT AS TO WHAT APPLIES.
- 7. ALL KNOWN SUBSURFACE UTILITIES AND STRUCTURES HAVE BEEN INDICATED ON THE PLAN(S) AS ACCURATELY AS POSSIBLE. THE EXACT LOCATION MAY VARY AND THE CONTRACTOR IS CAUTIONED TO PROCEED WITH CARE.
- 8. CONTRACTOR SHALL VERIFY ALL BENCH MARKS, INVERTS, PIPES AND STRUCTURES ELEVATIONS PRIOR TO START OF WORK. IMMEDIATELY NOTIFY SVE ASSOCIATES IF THE FIELD INFORMATION DOES NOT MATCH PLAN INFORMATION.
- 9. THE OWNER WILL PROVIDE BENCH MARKS. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL OTHER LAYOUT AND FOR REPLACEMENT OF LAYOUT COMPLETED BY THE OWNER.
- 10. CONTRACTOR SHALL PROVIDE A FULL SET OF AS-BUILT DRAWINGS TO THE OWNER WITH SWING TIES OR COORDINATES, LOCATING ALL FITTINGS, STRUCTURES, PIPES, ETC. THE AS-BUILTS SHALL INDICATE MATERIALS, PIPE LENGTHS INSTALLED, ALL INVERTS, AND ALL STRUCTURE
- ELEVATIONS. ACCEPTANCE OF THE WORK IS SUBJECT TO ACCEPTANCE OF THE AS-BUILTS BY THE ENGINEER AND OWNER.

 11. MONUMENTATION THAT HAS BEEN DISTURBED SHALL BE RESET BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR AT NO COST TO THE OWNER.
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DE-WATERING AT NO ADDITIONAL COST TO THE OWNER.
- 13. ALL SURFACES SHALL BE GRADED TO DRAIN.
- 14 ALL TREES WHOSE ROOTS HAVE BEEN DAMAGED SHALL BE REMOVED AT THE CONTRACTOR'S EXPENSE
- 15. THE CONTRACTOR SHALL RESTORE ALL DISTURBED SURFACES TO THEIR ORIGINAL CONDITION OR BETTER. ALL NEW AND EXISTING PIPES AND STRUCTURES SHALL BE CLEANED. ALL SIGNS SHALL BE REPLACED. ALL DAMAGED VEGETATION SHALL BE REPLACED.

SEDIMENT AND EROSION CONTROL NOTES:

- 1. INSTALL ALL SEDIMENT & EROSION CONTROL MEASURES IN ACCORDANCE WITH MANUFACTURER'S DIRECTION OR DETAILS PROVIDED. PERIMETER CONTROLS MUST BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR ALL EROSION CONTROL. THEY SHALL TAKE ALL MEASURED NEEDED TO MINIMIZE EROSION TO THE GREATEST EXTENT POSSIBLE, AT NO COST TO THE OWNER, REGARDLESS OF DETAIL SHOWN ON THESE PLANS.
- 3. THE CONTRACTOR SHALL INSPECT AND REPAIR ALL SEDIMENT AND EROSION CONTROL MEASURES DAILY WHILE UNDER CONSTRUCTION, THEN AFTER EACH RAINFALL OF 0.5" IN 24 HOURS AND NOT LESS THAN ONCE A WEEK THEREAFTER UNTIL ALL UPHILL SOILS ARE WELL STABILIZED.
- 4. SEED, FERTILIZE & MULCH ALL FINISH GRADED AREAS WITHIN 72 HOURS OF FINISH GRADING. ROADWAY STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISH GRADE.
- 5. SEDIMENT CONTROLS AND/OR SILT FENCES SHALL BE REPLACED WHEN CLOGGED AND NO LONGER FUNCTIONAL
- 6. SEDIMENT CONTROLS AND/OR SILT FENCES SHALL REMAIN IN PLACE UNTIL ALL UPHILL VEGETATED AREAS ARE STABILIZED.
- 7. ALL SOIL STOCKPILES SHALL BE SEEDED AND MULCHED IF LEFT IN PLACE MORE THAN 21 DAYS. 8. SEEDING OF ALL DISTURBED AREAS SHALL BE COMPLETED NOT LATER THAN OCTOBER 15TH.
- 9. STABILIZATION OF ALL WORK AREAS SHALL BE COMPLETED NOT MORE THAN 45 DAYS FOLLOWING THE START OF WORK.
- 10. ALL SOIL SLOPES STEEPER THAN 3: 1 SHALL BE COVERED WITH EROSION CONTROL FABRIC, S150 FROM NORTH AMERICAN GREEN OR APPROVED
- 11. STABILIZE ALL DRAINAGE SWALES, BASINS, BERMS AND DITCHES PRIOR TO DIRECTING RUNOFF TO THEM.
- 12. CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE SEDIMENT AND EROSION CONTROLS AS REQUESTED BY THE ENGINEER.
- 13.LIMIT THE AREA OF DISTURBANCE TO SMALLEST PRACTICAL AREA.
- 14.LOT CONSTRUCTION SHALL NOT COMMENCE UNTIL AFTER ASSOCIATED ROADWAY AND DRAINAGE IS COMPLETE AND STABLE.

WINTER CONSTRUCTION REQUIREMENTS:

- 1. ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND 1) INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, or 2) PLACING 3 TO 4 TONS OF MULCH PER ACCUMULATED SHOW ON FROZEN FOR THAN SHALL NOT OCCUR OVER ACCUMULATED SHOW ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF SPRING THAW OR
- ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
- 3. AFTER OCTOBER 15th, INCOMPLETE ROAD OR PARKING SURFACES WHERE WORK HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL MEETING NIDOT ITEM 304.3 SPECIFICATIONS.

PROJECT SPECIFIC NOTES:

- 1. ALL STORM DRAIN TO BE HIGH DENSITY SMOOTH BORE POLYETHYLENE, HANCOR OR APPROVED EQUAL, U.N.O.
- 2. ALL AREAS TO BE VEGETATED SHALL RECEIVE A MINIMUM OF 6" OF LOAM, SEED AND MULCH. IF PLANS OR SPECIFICATIONS HAVE CONFLICTING DEPTHS OF LOAM, 6" OF LOAM SHALL BE THE PREVAILING DEPTH USED.
- 3. SEEDING OF ALL DISTURBED AREAS SHALL BE COMPLETED NOT LATER THAN OCTOBER 15Th
- 4. SEEDING OF ALL FINISHED AREAS SHALL BE COMPLETED NOT MORE THAN 72 HOURS AFTER FINISH GRADING.
 5. STABILIZATION OF ALL WORK AREAS SHALL BE COMPLETED NOT MORE THAN 45 DAYS FOLLOWING THE START OF WORK.
- BROOM, WASH AND APPLY TACK COAT TO BASE PAVEMENT PRIOR TO WEAR COURSE PLACEMENT.
- 7. STABILIZE ALL DRAINAGE SWALES PRIOR TO DIRECTING RUNOFF TO THEM.
- 8. PER RSA 79:10 IF TREE CUTTING EXCEEDS 10,000 BOARD FEET OR OVER 20 CORDS OF FUEL WOOD, CONTRACTOR SHALL FILE "NOTICE OF INTENT TO CUT WOOD OR TIMBER" WITH LOCAL AUTHORITY & PAY TAXES AS NEEDED.

SEQUENCE OF WORK:

THE SEQUENCE OF WORK SHALL BE FOLLOWED WITHIN EACH PHASE OF THE PROJECT. AT NO TIME OR PLACE SHALL PROJECT PHASING SUPERCEDE SOUND SEDIMENT AND EROSION CONTROL PLANNING.

- 1. INSTALL SILT FENCE IN ACCORDANCE WITH MANUFACTURER'S DIRECTIONS, IN LOCATIONS DETAILED ON THIS PLAN OR AS ORDERED BY THE ENGINEER.
- 2. CONSTRUCT THE STABILIZED CONSTRUCTION ENTRANCE TO PREVENT TRACKING OF SEDIMENT OFFSITE
- 3. CONSTRUCT AND STABILIZE THE DETENTION CONTROLS AND ALL INLET/OUTLET SWALES.
- 4. CLEAR AND GRUB THE DRIVEWAY CORRIDOR.
- 5. INSTALL WELL FOLLOWED BY OTHER UTILITIES.
- 6. CONSTRUCT DRIVE IN ACCORDANCE WITH APPROVED PLANS.
- 7. CLEAR & GRUB HOUSE/PARKING AREA. CONSTRUCT NEW PARKING LOT AND HOUSES.
- 8. LOAM AND SEED DISTURBED AREAS, STABILIZE SLOPES WITH MATTING WHERE SPECIFIED.
- 9. REMOVE SILT FENCE AFTER ALL UPHILL SOILS ARE STABILIZED.

DUST CONTROL:

DUST CONTROL SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NEW HAMPSHIRE STORMWATER MANUAL, VOLUME 3: EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION.

1. PHASE CONSTRUCTION AND SEQUENCE EARTH DISTURBANCE ACTIVITIES TO REDUCE THE AREA OF LAND DISTURBED AT ANY ONE TIME.

2. MAINTAIN AS MUCH NATURAL VEGETATION AS IS PRACTICABLE.

3. USE TRAFFIC CONTROL TO RESTRICT TRAFFIC TO PREDETERMINED ROUTES.

4. USE TEMPORARY MULCHING, PERMANENT MULCHING, TEMPORARY VEGETATIVE COVER, PERMANENT VEGETATIVE COVER TO REDUCE THE NEED FOR DUST CONTROL.

- APPLY WATER, OR OTHER DUST INHIBITING AGENTS OR TACKIFIERS, AS APPROVED BY THE NHDES.

SITE DATA TABLE

TAX MAP # 503-005-000-0000 309,276 SQ. FT. ± 7.1± ACRES

ZONE: RESIDENTIAL

AVAILABLE REQUIRED: LOT SIZE: 7.1+ ACRES 2 AC FRONTAGE: 00 FEET 50 FEET 200 FEET

NONE

PROPOSED: LESS THAN 35 FEET ALLOWED: BLDG. HEIGHT: 35 FEET

BUILDING SETBACKS: FRONT: 50' REAR: 50' SIDES: 50'

LOT WIDTH:

PAVEMENT SETBACKS: PARKING AREA: < 10.000 SE FRONT/SIDE/REAR:

LOT COVERAGE: MAXIMUM PROPOSED: 10% (30.928 SE/0.71 AC) 1% (1.914 SE/0.04 AC) BUILDINGS: 20% (61,855 SF/1.42 AC) 1% (4.040 SF/0.09 AC) PAVEMENT: 2% (5,954 SF/0.14 AC) TOTAL IMPERMEABLE: 20% (61.855 SF/1.42 AC)

PARKING: REQUIRED: PROPOSED: 9' X 18' 2 SPACES /UNIT

SEED SPECIFICATIONS PERMITS REQUIRED: CITY OF KEENE, SITE PLAN REVIEW

TEMPORARY SEED

PERENNIAL RYE GRASS

2 NHDES SUBSURFACE DESIGN REVIEW 3. NHDES SUBDIVISION REVIEW

PERMANENT SEED:

ALL MOWABLE AREAS: PARK SEED NHDOT TYPE 15 (CONSERVATION MIX ACCEPTABLE, AS APPROVED BY ENGINEER)

CREEPING RED FESCUE PERENNIAL RYEGRASS 50 LB/AC KENTUCKY BLUEGRASS 25 LB/AC 5 LB/AC TOTAL: 120 LB/AC

ALL SLOPES 5:1 OR STEEPER: SLOPE SEED NHDOT TYPE 45 (OR OTHER WILDFLOWER MIX APPROVED BY ENGINEER)

PERENNIAL RYEGRASS 30 LB/AC REDTOP ALSIKE CLOVER 5 LB/AC LANCE-LEAVED CORFORSIS 5 LB/AC OXEYE DAISY BUTTERFLY WEED LB/AC 3 LB/AC BLACKEYED SUSAN 3 LB/AC WILD LUPINE 3 LB/AC

PROPERTY OWNER & APPLICANT:

MONADNOCK HABITAT FOR HUMANITY

P.O. BOX 21 KEENE NH 0.34.31


STABILIZATION DEFINITION:

AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:


1 BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED: A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED

95 LB/AC

- 2. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH STONE OR RIPRAP HAS BEEN INSTALLED; 4. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.



STONE DRIP STRIP SCALE: 1" = 1'




50' MIN.

> EXISTING


PA VEMENT


STABILIZED CONSTRUCTION ENTRANCE



EROSION CONTROL MATTING SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S DIRECTIONS, THIS IS ONLY A GUIDELINE.
ROLL OUT MATTING DOWNHILL AND STAPLE AS REQUIRED FOR SLOPE. MATTING SHOULD OVERLAP BY A MINIMUM OF 4 INCHES AND STAPLED AT THE EDGE OF EACH ROLL.


EROSION CONTROL BLANKET





PIPE IN TRENCH DETAIL






Engineering Planning Landscape Architecture Surveying


SVE Associates P.O. Box 1818 439 West River Road Brattleboro, VT 05302 T 802.257.0561 F 802 257 0721 www.sveassoc.com

NOTES & DETAILS


HABITAT FOR HIIMANITY

MONADNOCK HABITAT P.O. BOX 21 KEENE, NEW HAMPSHIRE









SWANZEY

NO. REVISION DATE DWN CHK

SVE ®


Engineering
Planning
Landscape Architecture
Surveying


SVE Associates
P.O. Box 1818
439 West River Road
Brattleboro, VT 05302
T 802.257.0561
F 802.257.0721
www.sveassoc.com

LOT 1 SEPTIC

HABITAT FOR HUMANITY

MONADNOCK HABITAT
P.O. BOX 21
KEENE, NEW HAMPSHIRE






123/456 DEED VOLUME & PAGE

CHESTERFIELD

MARLBOROUGH

SWANZEY



S 46°29'33" E

118.45

PROPOSED LOT 5.2 4.82 ±ACRES

T RUNORF AWAY KOM

INSULATION OVER

PIPE DETAIL

EXCLUDED FROM LOT LOADING AREA

46°38 1

OLD WALPOLE ROAD

ENVIRO-SEPTIC PIPE

LIQUID LEVEL

Engineering Planning Landscape Architecture

> Surveying SVE Associates P.O. Box 1818 439 West River Road Brattleboro, VT 05302

T 802.257.0561 F 802.257.0721 www.sveassoc.com



HABITAT FOR

HUMANITY MONADNOCK HABITAT

P.O. BOX 21 KEENE, NEW HAMPSHIRE

